



Alan Bell Architect, Inc.
ARCHITECTURE~ENGINEERING~PLANNING

Project # 11060-A11
Carrollton, Georgia

Addendum No. 3

Date: July 5, 2011

This addendum shall supersede all contract and/or conflicting information contained in the plans and specifications. Plans and specifications are hereby amended in the following particulars.

A New Amphitheater for City of Carrollton

- Item 1 Refer to sheet A-7. Cast-in-place concrete footing for the 10" thick concrete stage wall shall be 2'-10" wide as specified on detail 1/A-7 in lieu of 4'-0" wide as specified on Stage Foundation Plan.
- Item 2 Refer to sheet A-7. Cast-in-place concrete footing for the 2'-0" thick concrete wall, located adjacent to the stage, shall be 10'-0" wide as specified on Stage Foundation Plan in lieu of 12'-0" wide as specified on detail 1/A-7.
- Item 3 Refer to Architectural drawings and Project Manual, 05120 Structural Steel. Welding contractor, fabricators and erectors shall be AISC certified for all required project steel installations.
- Item 4 Refer to Architectural drawings and Project Manual, 07610 Metal Roofing. Warranties as described in specification 07610 Metal Roofing shall be provided by the manufacturer of the metal roofing material. General contractor's or subcontractor's warranty substitution will not be accepted.

End of Addendum #3
7/05/2011